

PATTON RD. AND BEACH BLVD. SERVICE RD.

BUFFER ZONE 1 TREE SCHEDULE (TREES IN THESE AREAS WILL BE PART OF IRRIGATION PLAN)

QTY	TREE VARIETY	DESCRIPTION	UNIT PRICE	EXTENDED
14	<i>PINUS PALUSTRIS</i> LONGLEAF PINE	4" CAL. 12' HT., 4' SPD. DENSE	\$464.91	\$6,508.74
24	<i>MAGNOLIA GRANDIFLORA</i> SOUTHERN MAGNOLIA 'DD BLANCHARD'	6" CAL. 16' HT., 8' SPD.	\$847.48	\$20,339.52
29	<i>JUNIPERUS SILICICOLA</i> SOUTHERN REDCEDAR	5" CAL. 14-16' HT., 7' SPD. DENSE	\$758.87	\$22,007.23

BUFFER ZONE 2 TREE SCHEDULE (TREES IN THESE AREAS WILL BE PART OF IRRIGATION PLAN)

QTY	TREE VARIETY	DESCRIPTION	UNIT PRICE	EXTENDED
5	<i>MAGNOLIA GRANDIFLORA</i> SOUTHERN MAGNOLIA 'DD BLANCHARD'	4" CAL. 12' HT., 6' SPD.	\$499.31	\$2,496.55
5	<i>PINUS PALUSTRIS</i> LONGLEAF PINE	4" CAL. 12' HT., 4' SPD. DENSE	\$464.91	\$2,324.55
8	<i>JUNIPERUS SILICICOLA</i> SOUTHERN REDCEDAR	3" CAL. 10' HT., 4' SPD. DENSE	\$359.63	\$2,877.04

RESIDENTIAL RIGHT OF WAY TREE SCHEDULE

QTY	TREE VARIETY	DESCRIPTION	UNIT PRICE	EXTENDED
8	<i>QUERCUS VIRGINIANA</i> LIVE OAK	3" CAL. 10' HT.	\$566.03	\$4,528.24
2	<i>MAGNOLIA GRANDIFLORA</i> SOUTHERN MAGNOLIA 'LITTLE GEM'	3.5" CAL. 10' HT.	\$499.31	\$998.62
6	<i>ILEX VOMITORIA</i> 'PRIDE OF HOUSTON' YAUPON HOLLY	MIN. 3 TRUNKS @ 8' HT.	\$293.96	\$1,763.76

SUBTOTAL

\$63,844.25


ADDITIONAL SERVICES

IRRIGATION DESIGN AND INSTALLATION ON BUFFER ZONES 1 AND 2			\$20,548.49
REPLACEMENT OF UNSUITABLE SOILS ON (24) 3" CALIPER TREES	22.48CF ADDITIONAL SOIL AT \$74.22/CY		\$1,482.92
ADDITIONAL ONE YEAR WARRANTY - 12% OF TOTAL COST			\$7,661.31
SUPPLEMENTAL FERTILIZATION - END OF YEAR ONE	6-10' CANOPY SPD (0.5LB)	\$2.96/101 TREES	\$298.96
SUPPLEMENTAL FERTILIZATION - END OF YEAR TWO	10-12' CANOPY SPD (0.75LB)	\$4.43/101 TREES	\$447.43

\$94,283.36

PRICE PROPOSAL PER DAVEY CONTRACT #7660-01

PREPARED BY KATHLEEN MCGOVERN/CITY ARBORIST/PUBLIC WORKS



VICINITY MAP - NOT TO SCALE

PATTON RD. AND BEACH BLVD. SERVICE RD.

BUFFER ZONE 1 TREE SCHEDULE (TREES IN THESE AREAS WILL BE PART OF IRRIGATION PLAN)

QTY	TREE VARIETY	DESCRIPTION
14	<i>PINUS PALUSTRIS</i> LONGLEAF PINE	4" CAL. 12' HT., 4' SPD. DENSE
24	<i>MAGNOLIA GRANDIFLORA</i> SOUTHERN MAGNOLIA 'DD BLANCHARD'	6" CAL. 16' HT., 8' SPD.
29	<i>JUNIPERUS SILICICOLA</i> SOUTHERN REDCEDAR	5" CAL. 14-16' HT., 7' SPD. DENSE

BUFFER ZONE 2 TREE SCHEDULE (TREES IN THESE AREAS WILL BE PART OF IRRIGATION PLAN)

QTY	TREE VARIETY	DESCRIPTION
5	<i>MAGNOLIA GRANDIFLORA</i> SOUTHERN MAGNOLIA 'DD BLANCHARD'	4" CAL. 12' HT., 6' SPD.
5	<i>PINUS PALUSTRIS</i> LONGLEAF PINE	4" CAL. 12' HT., 4' SPD. DENSE
8	<i>JUNIPERUS SILICICOLA</i> SOUTHERN REDCEDAR	3" CAL. 10' HT., 4' SPD. DENSE

RESIDENTIAL RIGHT OF WAY TREE SCHEDULE

QTY	TREE VARIETY	DESCRIPTION
8	<i>QUERCUS VIRGINIANA</i> LIVE OAK	3" CAL. 10' HT.
2	<i>MAGNOLIA GRANDIFLORA</i> SOUTHERN MAGNOLIA 'LITTLE GEM'	3" CAL. 10' HT.
6	<i>ILEX VOMITORIA</i> 'PRIDE OF HOUSTON' YALPON HOLLY	MIN. 3 TRUNKS @ 8' HT.



TREES IN THESE LOCATIONS WILL BE AREAS UNDER PERMANENT IRRIGATION

TREE PLANTING PLAN

PATTON ROAD AND BEACH BLVD. SERVICE RD.
CITY OF JACKSONVILLE - PUBLIC WORKS
NOT TO SCALE - SHEET 1 OF 1

